higher education & training

Department:
Higher Education and Training
REPUBLIC OF SOUTH AFRICA

T90**(E)**(A1)T

NATIONAL CERTIFICATE

BUILDING ADMINISTRATION N4

(4090034)

1 April 2019 (X-Paper)
09:00–12:00

This question paper consists of 5 pages.

Copyright reserved

DEPARTMENT OF HIGHER EDUCATION AND TRAINING
REPUBLIC OF SOUTH AFRICA

NATIONAL CERTIFICATE
BUILDING ADMINISTRATION N4
TIME: 3 HOURS
MARKS: 100

INSTRUCTIONS AND INFORMATION

1. Answer ALL the questions.
2. Read ALL the questions carefully.
3. Number the answers according to the numbering system used in this question paper.
4. Write neatly and legibly.

Copyright reserved

QUESTION 1

Complete the following sentences by filling in the missing word or words. Write only the words next to the question number (1.1–1.10) in the ANSWER BOOK.

1.1 A … is used to make holes for screws.

1.2 The workshop must have … to suck out and remove the saw dust.

1.3 Every workshop should have a… for sharpening blades.

1.4 After the doors have been assembled, they are smoothed off using a…

1.5 … are used for cutting out mouldings and recesses for hinges and mortice locks when hanging doors.

1.6 The tongue and grooves are cut with a…

1.7 In a workshop where wooden doors are manufactured, the first machines that are to be used will be a variety of…

1.8 Door stile mortices are cut using a…

1.9 A … produces two adjacent smooth sides to the lengths of the timber.

1.10 A … is used to cut the long pieces of timber across the grain.

(10 × 1) **[10]**

QUESTION 2

Complete the following sentences by using the words in the list below. Write only the word or words next to the question number (2.1–2.10) in the ANSWER BOOK

buyer; general foreman; artisans; quantity surveyor; personnel department; building surveyor; costing clerk; contractor; estimator; valuation

2.1 After the tender is accepted and the necessary contract documents are signed, the builder will be called a …

2.2 On site the … is in charge of all construction carried out.

2.3 Trades foremen oversee particular groups of … labourers.

2.4 For the building work, the … must place all orders in good time for the material and plant to arrive on site on time.

2.5 The … must see to it that sufficient labour and control staff are employed.

2.6 At frequent intervals, the … analyses actual costs of all work done/completed.

Copyright reserved

2.7 The … of the building firm uses the actual rates when tendering again for a future contract.

2.8 The architect must certify the … before payment can be made.

2.9 After a stipulated lapse in time, the … will claim an interim payment from the client.

2.10 The … who is an advisor of the employer, must check the claim by evaluating the work done to date.

(10 × 1) **[10]**

QUESTION 3

State the important factors that must be considered when planning each of the following:

3.1 Access roads

3.2 Plant and machinery

(2 × 5) **[10]**

QUESTION 4

Make a neat, labelled sketch of a truss-out scaffold (cantilever). **[12]**

QUESTION 5

Explain the use of each of the following documents when handling building materials:

5.1 Order form

5.2 Delivery note

5.3 Requisition

5.4 Receipt

5.5 Invoice

(5 × 2) **[10]**

Copyright reserved

QUESTION 6

6.1 Define a *programme.* (2)

6.2 State SEVEN purposes for the use of a programme. (9)

6.3 Name SIX important duties of the supervisor on site. (6)

6.4 Name the document used to hand in the quotation when tendering. (1)

[18]

QUESTION 7

Use half of the page to sketch each of the following documents:

7.1 Order form

7.2 Internal requisition

(2 × 6) **[12]**

QUESTION 8

The load on an existing building is to be increased and therefore the building must be underpinned.

Sketch and explain the method of underpinning using the jack and precast reinforced concrete piles. **[10]**

QUESTION 9

State the main duty of each of the following members of a medium-size building firm:

9.1 Estimator

9.2 Engineer

9.3 General foreman

9.4 Accountant

(4 × 2) **[8]**

TOTAL: 100

Copyright reserved