higher education & training

Department:
Higher Education and Training
REPUBLIC OF SOUTH AFRICA

MARKING GUIDELINE

NATIONAL CERTIFICATE

BUILDING ADMINISTRATION N5

3 DECEMBER 2019

This marking guideline consists of 7 pages.

Copyright reserved

QUESTION 1

1.1 Buying
1.2 Delivery invoice
1.3 Storekeeper/store clerk
1.4 Theft
1.5 Care
1.6 Work area/working site
1.7 Moisture
1.8 Toxic
1.9 Fragile/easily damaged
1.10 Damaged/stolen

(10 × 1) **[10]**

QUESTION 2

2.1 Tradesforeman
2.2 Storekeeper
2.3 Artisan
2.4 Surveyor
2.5 Nominated subcontractor
2.6 General foreman
2.7 Building control officer
2.8 Building surveyor
2.9 Clerk of works
2.10 Resident engineer

(10 × 1) **[10]**

QUESTION 3

3.1 True
3.2 True
3.3 True
3.4 False
3.5 True
3.6 True
3.7 True
3.8 False
3.9 False
3.10 False

(10 × 1) **[10]**

Copyright reserved

QUESTION 4

4.1 A conveyor belt is used for filling up aggregate bins in weigh batchers or moving excavated soil for loading to be transported.

4.2 A dragline is used for excavating loose and soft soil below the level of the machine.

4.3 A grader is used for finishing fine limits in large areas of ground which have been scraped or bulldozed to the required formation level.

4.4 A backacter is probably the most common form of excavating basements, pits and trenches.

4.5 A tractor shovel's primary function is to scoop up loose material in the bucket, raise the loaded spoil and to manoeuvre into position to discharge the load into an attendant lorry or dumper.

4.6 A trencher is a machine designed to excavate trenches of constant width with considerable accuracy and speed.

4.7 A bulldozer is used for site clearing, i.e. felling down trees and site leveling.

4.8 A tipping lorry's primary function is moving or transporting spoil material in and out of the site where the dumping site is allocated.

4.9 A scraper consists of a power unit and a scraper bowl and is used to excavate and transport spoil where surface stripping, site leveling and cut and fill activities are planned.

4.10 A face shovel can be used as a loading shovel or for excavation into the face of an embankment.

(10 × 1) **[10]**

QUESTION 5

5.1 5.1.1 Program evaluation review technique

5.1.2 Graphical evaluation review technique

5.1.3 Precedence diagrammatic method

5.1.4 Arrow diagrammatic method

5.1.5 Work breakdown structure

(5 × 1) (5)

5.2 a – Activity identification
b – Earliest starting time
c – Earliest finishing time
d – Activity time
e – Latest starting time
f – Latest finishing time (5 × 1) (5)
[10]

QUESTION 6

6.1 Appointment
- By architect
- By main contractor as a party in the contract

Recognition
- By architect and main contractor
- Communication through general foreman
- Site meetings

Liability
- Nonsubcontractors are liable to the employer
- As per contract

Attendance
- Main contractor has to give attendance
- Such as assistance, water supply, et cetera

Payment
- Certified by architect
- Via main contractor
- Provisional/sum (Any 5 × 1) (5)

6.2 Appointment
- By main contractor with architect's permission
- By subtender

Recognition
- Only by main contractor
- Not by architect but must give permission
- Must comply with main contract

Liability
- Main contractor is liable
- Controlled by general foreman

Attendance
- By contract between subcontractor and main contractor

Payment
By main contractor (employer is not liable) (Any 5 × 1) (5)
[10]

Copyright reserved

QUESTION 7

- A big advantage to the programmer is that the job sequence or logic (order of logic) can be completely separated from the time element in the preparation of the plan.
- The critical activities are clearly shown and can be altered easily if other activities become critical because of delays.
- The noncritical activities can, with due examination, result in more economic use of resources.
- Noncritical activities can be delayed or performed more slowly so that resources may be used for more critical events, provided that they are not delayed so long that they are in turn becoming critical.
- The interrelationship between all the activities is clearly shown by the flow of the network. (5 × 2) **[10]**

QUESTION 8

8.1 A forecast is looking ahead, which is the best source of labour and plant, alternatives of buying and hiring plant and the cost of labour and materials. A library of standard data can be accumulated.

8.2 Planning depends on provisions of accurate information for success. A flow chart and string diagrams can be used to plan the site layout and basic data supplied as a result of method study and work measurement.

8.3 Organising is devising the most efficient relationship between labour and plant and involves the use of method study, while a check-up on the overall economy of production, is necessary to employ work measurement.

8.4 Coordinating is linking together the various members to constitute a practical ensemble and the balancing of resources and activities to ensure complete harmony at every performance.

8.5 Controlling is the accurate standard established by measurement to provide effective means of controlling machine utilisation and labour cost based on allowed times.

(5 × 2) **[10]**

Copyright reserved

QUESTION 9

General site meeting No:
To be held at place on date of time:

1 Welcome, introduction

2 Apologies for absence

3 Attendance register

4 Minutes

5 Matters arising from minutes

6 Main business

- 6.1 General problem areas
- 6.2 Variations
- 6.3 Progress
- 6.4 Subcontractors
- 6.5 Nominated subcontractors
- 6.6 Local authorities

7 General

- 7.1 ……
- 7.2 ……
- 7.3 …….

8 Date for next meeting

9 Closing

…….. ……..

Chairman Date **[10]**

QUESTION 10

10.1 Mandatory dependencies: These are dependencies that cannot change, such as erecting the walls of a house before putting up the roof.

10.2 Discretionary dependencies: These are dependencies that may be at the discretion of a project manager or may change from project to project.

10.3 The time differential between the scheduled completion date and the required date to meet the critical path is referred to as the slack time.

10.4 The time period between the early start or finish of one activity and the early start or finish of another in the sequential chain is called lag.

10.5 Resource levelling is an attempt to eliminate the manpower peak and valley by smoothing out the period-to-period resource requirement.

(5 × 2) **[10]**

TOTAL: 100

Copyright reserved