higher education & training

Department:
Higher Education and Training
REPUBLIC OF SOUTH AFRICA

# MARKING GUIDELINE

## NATIONAL CERTIFICATE

## BUILDING ADMINISTRATION N6

## 9 APRIL 2019

**This marking guideline consists of 4 pages.**

Copyright reserved

**NOTE:** Marks can be allocated for any relevant answer even if it does NOT appear in this marking guideline.

## QUESTION 1

1.1
- Avoidance of all forms of waste
- Finding better methods of working
- Improving the planning and organising of work
- Stimulating output by well-designed incentive schemes (4)

1.2
- Select
- Record
- Examine
- Develop
- Install
- Maintain (6)

1.3
- Time study
- Synthesis from elemental data
- Predetermined motion-time system
- Analytical estimating
- Activity sampling (5)

1.4
- Time for carrying out an element of work at standard rating✓✓
- Total time in which a task should be completed at standard performance✓✓
- Ensure productivity within a specified period✓ (5)

**[20]**

## QUESTION 2

2.1
2.1.1 True
2.1.2 True
2.1.3 True
2.1.4 True
2.1.5 True
2.1.6 False
2.1.7 False
2.1.8 False
2.1.9 False
2.1.10 True

(10 × 1) (10)

2.2
- Responsible
- Punctual
- Motivate
- Accountable
- Kind and polite
- Fair
- Understanding
- Nonjudgemental
- Honest
- Reliable (Any 5 × 2) (10)

**[20]**

**QUESTION 3**

3.1
- To pool the company's past experience and the various departments and specialists
- To assist the estimating department by delegating certain tasks to others
- To eliminate controversy between the estimator and supervisor on methods, output rates, preliminaries and costs
- To ensure realistic tenders by coordinating technical theory with current practice
- To improve ratio awards to submitted tenders (5 × 2) (10)

3.2
- Nature of contract
- Location of site
- Access to site
- Type of ground and water cables
- Existing services
- Labour availability
- Average weather conditions
- Form of contract
- Brief method appreciated covering bulk items
- Time allowed
- Whether site is fenced
- Access to the road
- Details of professionals
- Drawings available at time of tender (Any 10 × 1) (10)

**[20]**

Copyright reserved 

**QUESTION4**

4.1
- Point at which construction will start and general flow of the work
- Items of plant and location on-site
- Methods of bulk items of work
- Access to and about the site
- Location and necessity of storage areas (5 × 2) (10)

4.2
- Nature and scope of the project
- Access to the site
- Type of ground and water table
- Existing services (material supplies, etc.)
- Location of site and getting to it
- Whether the site is fenced (hoarding)
- Average site conditions
- Power supply availability
- Form of contract
- Scaffolding and hoisting
- Schedule of nominated items
- Availability of labour (Any 10 × 1) (10)

**[20]**

**QUESTION 5**

5.1
- They do inspections and write reports of accidents that occurred.
- They attend health and safety meetings and give feedback to colleagues and workers.
- They advise the employer about hazardous situations at the workplace or report them to the employer.
- They monitor health and safety in the workplace.
- They represent the employees on behalf of the employer with regard to health and safety issues (spokesperson). (5 × 2) (10)

5.2
- Take reasonable care of the health and safety of himself/herself and of other persons who are under his/her instructions on site
- May be affected by his/her acts of omission
- Cooperate with the employer and his/her subordinates
- Carry out orders and obey health and safety rules
- Report unsafe and unhealthy situations
- Report accidents as soon as possible (Any 3 × 2) (6)

5.3
5.3.1 OHS
5.3.2 SDA
5.3.3 DoL
5.3.4 DHET

(4 × 1) (4)

**[20]**

**TOTAL: 100**

Copyright reserved