higher education & training

Department:
Higher Education and Training
REPUBLIC OF SOUTH AFRICA

MARKING GUIDELINE

NATIONAL CERTIFICATE (VOCATIONAL)

CONSTRUCTION PLANNING
NQF LEVEL 4

27 FEBRUARY 2019

This marking guideline consists of 7 pages.

Copyright reserved

QUESTION 1

1.1 1.1.1
- The *defects liability period* is the set period in which the contractor must fix or repair all defects.
- A typical defects liability period usually lasts 12 months.
- A defects liability period will only be effected if it was included in the contract.

1.1.2
- *Interim payments* are regular intervals at which payment is made to the contractor.
- These are usually paid monthly throughout the contract period until completion and hand over of construction project.

1.1.3
- A *tender* is a formal offer to do specific work for a stated fixed price.
- A tender may also be an opportunity for companies or institutions to bid for a project.
- A tender must be submitted within a given timeframe.
- It does NOT necessary mean that by putting a tender the job or project will be yours.

1.1.4
- The *contract sum* is the amount of money to be paid for the construction project, including tax, as accepted by the client.
- It is paid monthly on progression of the construction project.

1.1.5
- *Breach of contract* is the failure to execute and deliver what is required in the signed contract.
- It also implies that construction contractors failed to deliver works that meet the description and standard under the construction contract, which constitutes defective work.

(5 × 2) (10)

1.2 1.2.1 True
1.2.2 False
1.2.3 False
1.2.4 True
1.2.5 True

(5 × 1) (5)
[15]

QUESTION 2

2.1 2.1.1 E
2.1.2 A
2.1.3 B
2.1.4 C
2.1.5 D
2.1.6 F

(6 × 1) (6)

2.2
- A *contract* is a professional written or verbal agreement✓ that states and explains an agreement between two or more parties or people that is enforceable by law.✓
- An *agreement* is a formal written or verbal arrangement between two or more parties or people.✓ It is usually made over small decisions by taking someone's word.✓ (2 × 2) (4)

[10]

QUESTION 3

3.1 Construction Industry Development Board (1)

3.2
- JBCC Series 2000
- Fidic
- GCC
- NEC3 family of contracts (Any 1 × 1) (1)

3.3 3.3.1 The main contractor is the contractor that has been selected or nominated by the client✓ and enters into a contract with the client to do the construction project.✓

3.3.2 A subcontractor is a contractor that signs a contract with the main contractor✓ to do a specific job on the construction project.✓

3.3.3 A nominated subcontractor is a subcontractor that is selected by the client/employer✓ or is selected from a list of contractors supplied by the employer.✓

(3 × 2) (6)

3.4
- To build strictly according to the design of the building
- To strictly adhere to contract conditions (Any 2 × 1) (2)

[10]

QUESTION 4

4.1 *Tender adjudication process* is the evaluation of a valid tender✓ that has been submitted by a relevant contractor who wants to be appointed to undertake a project.✓ (2)

4.2
- Architect
- Quantity surveyor
- Structural engineer
- Resident engineer (Any 3 × 1) (3)

4.3
- The contract
- The plans/drawings
- Bill of quantities
- Specifications
- Nominated subcontractors
- Nominated suppliers
- Form of tender (Any 5 × 1) (5)

4.4 As part of the project documentation the Bill of Quantities is very critical✓ as the cost of all items✓ will have a rate which is included in the bill of quantities✓ which can be used by the contractor and the client✓ for any changes to the contract.✓ (Any 3 × 1) (3)

4.5 4.5.1 South African Revenue Service

4.5.2 Value-added tax

(2 × 1) (2)
[15]

QUESTION 5

5.1
- Only a few selected construction companies are invited to tender
- Their selection is based on their track record and ability to execute the works
- The selection is also based on their expertise to for the scope and nature of the project
- Past performance on similar projects will also allow the client to invite these builders.
- Their financial security to deliver the works. (Any 4 × 1) (4)

5.2 5.2.1 $A_T = 2(l \times h) + 2(b \times h)$

$= 2(12 \times 2,4) + 2(8 \times 2,4)$ ✓

$= 57,6 + 38,4$ ✓

$= 96 \ m^2$ (4)

5.2.2 $\text{No. of bricks} = A \times Bricks / m^2$ ✓✓

$= 96 \times 104$ ✓

$= 9\ 984 \ bricks$ ✓ (2)

5.2.3 $A_{door} = 2,03 \times 0,81$
$= 1,644m^2$ ✓

$A_{windows1} = 5(1,2 \times 1,2)$
$= 7,2m^2$ ✓

$A_{windows\ 2} = 0,6 \times 0,6$
$= 0,36m^2$ ✓

$A_{window\ 3} = 2 \times 1,2$
$= 2,4m^2$ ✓

$A_{total} = 1,644 + 7,2 + 0,36 + 2,4$
$= 11,604m^2$ ✓ (5)

5.2.4 $A_{required} = 96 - 11,604$
$= 84,396m^2$

$No.\ of\ \ bricks = 84,396 \times 104$
$= 8\ 777,184$ ✓
$= 8\ 778\ \ bricks$ (3)

5.2.5 ✓
$\text{Cost} = \text{Price} \times \text{No. of bricks}$
$= R7,56 \times 8\ 778$ ✓
$= R66\ 361,68$ ✓ ✓ (2)

[20]

QUESTION 6

6.1
- The contractor will save time.
- The contractor will save money.
- The contractor will complete the project without challenges.
- The contractor will not go over the budget because of delays. (4 x 1) (4)

6.2
6.2.1 Non-critical
6.2.2 Critical
6.2.3 Critical
6.2.4 Non-critical
6.2.5 Non-critical
6.2.6 Critical
6.2.7 Non-critical
6.2.8 Critical
(8 × 1) (8)

6.3
- Removing of all trees, shrubs and vegetation
- Setting out of building
- Excavation of foundation trenches
- Pouring of concrete in trenches
- Building the masonry plinth (foundation) walls
- Casting of concrete slab
- Building of superstructure
- Beam filling (8 x 1) (8)

[20]

QUESTION 7

		Week 1					Week 2					Week 3					Week 4					Week 5					Week 6					Week 7				
Activity	Days	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5	1	2	3	4	5
Site clearance	3																																			
Setting out of building	1				✓																															
Excavation of trenches	5									✓																										
Casting of concrete foundations and slab	2											✓																								
Super-structure brickwork	10																					✓														
Erection of roof	3																								✓											
Installation of doors and windows	5																													✓						
Plastering of internal walls and floor screeds	3																											✓								
Plastering of external walls	5																																		✓	
Painting of walls	2																																	✓		

FOR OVERALL CORRECT DAYS = 1✓+ 9✓ AS SHOWN [10]
TOTAL: 100

Copyright reserved